



NOTES:

1. ALL MOUNTABLE CURB AND GUTTER CONCRETE SHALL BE SHA MIX NO. 3, 3,500 PSI - 28 DAY COMPRESSION STRENGTH.

2. PROVIDE REVERSE LIP GUTTER PAN TO MATCH ADJACENT PAVEMENT WHERE WATER FLOWS AWAY FROM CURB AND WHERE CALLED FOR ON CONSTRUCTION DRAWINGS.

3. CURB HEIGHT SHALL BE ADJUSTED AND SET OUT ON CONSTRUCTION DRAWINGS. MINIMUM HORIZONTAL TRANSITION FROM 6" TO 8" HEIGHT IS 10'.

△ 4. ALL METHODS OF CONSTRUCTION AND LOCATIONS OF CONSTRUCTION OR CONTRACTION JOINTS SHALL BE CONSISTENT WITH CURRENT MARYLAND STATE HIGHWAY ADMINISTRATION'S "STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS".

DPW\VOL1\CAD\1 QAC Road Standards\FINAL\MOUNTED_CURB_DETAIL_103.01_2026.DWG

APPROVED

1/22/26
DATE

Alan L. [Signature]
DIRECTOR, DEPT. OF PUBLIC WORKS

R. [Signature]
CHIEF ROADS ENGINEER

SCALE:
NO SCALE

REVISIONS:
△ JAN. 20, 2026

QUEEN ANNE'S COUNTY
DEPARTMENT OF PUBLIC WORKS

MOUNTABLE CURB DETAIL

STANDARD NO. RD-103.01