



NOTES:

1. CONCRETE SHALL BE SHA MIX NO. 2, 3,000 PSI - 28 DAY COMPRESSIVE STRENGTH.
2. STABILIZED SUB-BASE SHALL BE 4 INCHES MINIMUM COMPACTED BANK RUN GRAVEL (OR APPROVED EQUAL) PLACED AND COMPACTED ON APPROVED SUBGRADE TO 95% OF THE MODIFIED PROCTOR DENSITY FOR THE MATERIAL.
3. ALL AREAS WITHIN THE RIGHT-OF-WAY AND EASEMENTS SHALL BE GRADED TO PROVIDE POSITIVE DRAINAGE TO ROADWAY DRAINAGE SYSTEMS AND STABILIZED WITH A MINIMUM OF 4 INCHES OF TOPSOIL, SEEDED AND MULCHED PER NRCS SPECIFICATIONS.
4. SIDEWALKS TO BE MAINTAINED BY PROPERTY OWNER.
5. ALL METHODS OF CONSTRUCTION SHALL BE IN COMPLIANCE WITH QUEEN ANNE'S COUNTY STANDARDS. ALL MATERIAL SPECIFICATIONS SHALL COMPLY WITH THE 2001 EDITION OF THE MARYLAND STATE HIGHWAY ADMINISTRATION'S "STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS" MANUAL AND ANY ADDENDUM THERETO.

QUEEN ANNE'S COUNTY DEPARTMENT OF PUBLIC WORKS  <b>RESIDENTIAL SIDEWALK</b>	
APPROVED _____ DATE 1-2-03 ACTING DIRECTOR, DEPT. OF PUBLIC WORKS _____ CHIEF ROADS ENGINEER	SCALE: NO SCALE REVISIONS:
STANDARD NO. RD-104.01	